

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-20798-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 3-10S-26W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: ZIEGLER Well #: 3  
County: SHERIDAN Total Vertical Depth: 4100 feet

Operator License No.: 32322  
Op Name: DENIS F. ROBERTS  
Address: 3904 FAIRWAY DR BOX 1252  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	300	0	200 SX
PROD	5.5	4097	0	150 SX

133.25

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/18/2009 9:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: DENIS ROBERTS Company: DENIS F. ROBERTS Phone: (785) 625-8526

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 10/100 sxs gel - 800# hulls.  
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/18/2009 12:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 300' w/200 sxs cement.  
5 1/2" production casing set at 4097' w/150 sxs cement.  
Alternate II completion.  
Cement circulated to surface from 1930' with 450 sxs.  
Ran tubing to 3800' - pumped 10 sxs gel followed with 75 sxs cement with 600# hulls.  
Pulled tubing to 2260' - pumped 125 sxs cement mixed with 100# hulls.  
Pulled tubing to 1100' - pumped 135 sxs cement mixed with 100# hulls.  
Cement to surface. Pulled tubing to surface.  
Topped production casing with 40 sxs cement.  
Connected to 8 5/8" surface casing - pumped 6 sxs cement.  
Max. P.S.I. 500#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
4052	4055		

**INVOICED**  
DATE 1-12-10  
INV. NO. 2010060715

RECEIVED  
DEC 03 2009

Remarks: S.O.S. CEMENTING COMPANY-TICKET #408.

KCC WICHITA

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

RAINS & WILLIAMSON  
OIL COMPANY, INC.

220 W. DOUGLAS, 435 PAGE CT.

#3 ZIEGLER

3-10-26W  
SW NW SE


WICHITA, KS 67202

CONTR COMPANY TOOLS

CTY SHERIDAN

GEOL

FIELD FULLER NE



ELV 2597 KB SPD 3/5/85 CARD ISSUED 5/2/85 IP P 93 BO & 50 BWPD  
2588 GL DRLG COMP 3/16/85 LKC 4052-4055

LOG	Tops	Depth/Datum	API 15-179-20,798
ANH	.....	2221 + 376	8 5/8 " 300 / 200SX, 5 1/2 " 4097 / 150SX
B/ANH	.....	2260 + 337	DST (1) 3813-3848 (SHAW, LANS) / 30-30-30-30, (1ST OP) WB, (2ND OP) NB, REC 12' OIL SPKD M, W / SO IN TOP OF TOOL, SIP 455-477#, FP 33-33 / 33-33#
TOP	.....	3593- 996	DST (2) 3843-3868 (SHAW, LANS) / MISRUN
HEEB	.....	3813-1216	DST (3) 3810-3868 (SHAW, LANS) / 30-30-30-30, (1ST OP) FB / 2", (2ND OP) WB, REC 63' VSOCM, W / SO TOP OF TOOL, SIP 1085-1065#, FP 33-33 / 44-55#
TOR	.....	3841-1244	DST (4) 3873-3895 (LKC) / 30-30-60-30, WK TO SB BOTH OPNS, 200' GIP, REC 8' FREE OIL (GR 37%), 64' O & WCM (90% M, 5% OIL, 5% W), 63' M & OCW (25% M, 5% OIL, 70% W), SIP 997-975#, FP 33-55 / 55-88#
LANS	.....	3852-1255	DST (5) 3890-3910 (LKC) / 30-30-60-30, WK TO SB BOTH OPNS, 150' GIP, REC 40' SLI GSY OIL (GR 36%), 20' OCM (90% M, 10% OIL), SIP 931-865#, FP 44-44 / 44-55#
BKC	.....	4084-1487	
RTD	.....	4100-1503	

COPYRIGHT 1984  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)

RAINS & WILLIAMSON OIL COMPANY, INC. #3 ZIEGLER

3-10-26W  
SW NW SE

DST (6) 3915-3954 (LKC) / 30-30-60-30, (1ST OP) SB / 10", (2ND OP) SB / 17", REC 1140' SOCMW, 10' M, SIP 1075-1052#, FP 55-166 / 211-385#

DST (7) 3969-3975 (LKC) / 30-30-60-60, (1ST OP) SB / 1", (2ND OP) GTS / 45", REC 381' GSY OIL (GR 42%), 10' O & GCM (55% M, 30% G, 15% OIL), 62' O & GCM (40% M, 45% G, 15% OIL), 63' OCM (50% M, 5% G, 45% OIL), SIP 233-233#, FP 77-155 / 188-211#

DST (8) 4018-4042 (LKC) / 30-30-30-60, (1ST OP) WB, (2ND OP) NB, REC 8' M, W / OIL SCUM ON TOP, SIP 55-55#, FP 33-33 / 33-33#, BHT 121°

DST (9) 4040-4056 (LKC) / 30-30-60-45, SB, 2000' GIP, REC 628' GSY OIL (80% OIL-GR 38%, 20% G); 62' O & GCWM (80% M, 5% W, 5% OIL, 10% G), 62' WM (25% W, 75% M, SC OIL), 124' WM (80% W, 15% M), SIP 1185-1174#, FP 44-155 / 177-366#, BHT 123°

MIGT-CO, PF (LKC) 4052-4055, W / 4 SPF, SWB 7 BF (60% OIL) / 1ST HR, 8.25 BF (90% OIL) / 2ND HR, 8.5 BF (98% OIL) / LAST HR, FU, 2250' FL, SWB 7.5 BF (100% OIL), SWB 1800' OFF BTM, REC 2.25 BF (100% OIL), AC 250G, SWB DWN, REC 15.50 BF, W / TR OIL, SWB 5.75 BF (77% OIL) / 30", FU 3200' FL, 7 BF (100% OIL) / 1ST PULL, 4.75 BF (22% OIL) / 2ND PULL, SWB 8 BF (100% OIL) / 1ST HR, 6.5 BF (100% OIL) / 2ND HR, 5.5 BF (100% OIL) / 3RD HR, 5 BF (100% OIL) / 4TH HR, 7.5 BF (82% OIL) / 5TH HR, AC 750G, FU 2500' FL (50% OIL), SWB 7.5 BF (82% OIL) / 1ST HR, 6.5 BF (88% OIL) / 2ND HR, 8.25 BF (92% OIL) / 3RD, 7.5 BF (93% OIL) / 4TH HR, 8.02 BF (82% OIL) / 5TH HR, 7.02 BF (90% OIL) / 6TH HR, FU 2900' FL, 1 PULL 100% OIL, PULL PKR TO CMT PORT COLLAR, PF 3 / 1930, SQZ W / 450SX, PULL PKRS, DRILL CMT THRU PFS, T&R, POP, P 93 BO & 50 BWPD, 4/22/85

133-70