

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20718-00-00
Spot: NESW Sec/Twnshp/Rge: 26-25S-15W
3300 feet from N Section Line, 1980 feet from W Section Line
Lease Name: WADDLE Well #: 1
County: STAFFORD Total Vertical Depth: 4562 feet

Operator License No.: 5420
Op Name: WHITE & ELLIS DRILLING, INC.
Address: PO BOX 48848
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4200		WITH 2 SX CMT
SURF	8.625	292		WITH 200 SX CMT
UNK	4.5	4320		
PROD	4.5	4350	0	WITH 125 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/18/2009 11:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: DALLAS FLOWERS Company: WHITE & ELLIS DRILLING Phone: (316) 321-0550

Proposed Plugging Method: SET CIBP @ 4200' & 2 SX CMT. PERFORATE @ 960' & PUMP 100 SX CMT. PUMP 150 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS.
148.27

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2009 9:40 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SQUEEZED @ 989' WITH 150 SX CMT. SET CIBP @ 4200' & PUT 2 SX CMT ON TOP OF PLUG WITH DUMP BAILER. PERFORATED @ 960'. PUMPED 200 SX CMT. HAD CIRCULATION AT VERY START BUT SOON LOST IT. SDON. 11/19/09: TAGGED CMT INSIDE 4 1/2" @ 190' WITH TBG. PUMPED 20 SX CMT DOWN TBG CIRCULATING CMT TO SURFACE UP 4 1/2". PUMPED 150 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
4268	4272		
INVOICED			
DATE <u>1-12-10</u>			
INV. NO. <u>2010060719</u>			
RECEIVED DEC 07 2009 KCC WICHITA			

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED

NOV 23 2009

KCC DODGE CITY

KCC CP 243

PKT