

15-047-20650-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 28 TWP. 26S RGE. 16W E/W
Location as in quarters or footage from lines:
100' N of C NE SW

Lease Owner L.D. Drilling, Inc.
Lease Name Wells #3 (2-28) Well No. _____
Office Address Rt. 1 Box 183-B Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 6-3-82
Plugging completed 6-9-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom T.D. 4640'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	408'	none
				5-1/2"	4591'	2783'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cast Iron plug set @3986' and 5 sacks cement. Shot casing @3718', 3613', 3533', 3422', 3331', 3212', 3010', 2924' and 2806'. Pulled a total of 70 joints of 5-1/2" casing. Plugged well with 5 sacks hulls, 25 sacks gel, 140 sacks 50/50 pos, 2% gel, 3% cc.

Plugging Complete.

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1982

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling

CONSERVATION DIVISION
Wichita Kansas

STATE OF Kansas COUNTY OF Rice, ss:
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of June, 1982

My Commission expires:



Irene Hoover
Notary Public.

15-047-20650-00-00

WELL LOG
Wells #3 (2-28)
S/2 Sec. 29-26S-16W
Edwards County, Kansas

Name of Operator: Production, Inc.
2200 Lakin - Box 459
Great Bend, Kansas 67530
Date Completed: April 6, 1980

FROM	TO	
0	412	Surface
412	1160	Red Bed and Sand
1160	2770	Shale and Sand
2770	4005	Shale and Lime
4005	4640	Lime
4640		Total Depth

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1982
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
COUNTY OF BARTON ss

George E. Miller, Jr., President of Blue Goose Drilling Co., Inc.,
being first duly sworn on oath says: That I have knowledge of the facts,
statements and matters herein contained and the log of the above described
well as filed and that the same are true and correct.

George E. Miller, Jr.
George E. Miller, Jr.

Subscribed and sworn before me this 8th day of April, 1980.

Mary Ann Schwaborn
Notary Public Barton County

My commission expires 8-1-81.

