

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31569
Name: Bach Oil Production
Address 1: P.O. Box 723
Address 2: _____
City: Alma State: NE Zip: 68920 + _____
Contact Person: Jason Bach
Phone: (785) 476-5254
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: E175990003 Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 147-20161 - 0001
Spot Description: center
n.w.s.e.w Sec. 15 Twp. 1 S. R. 18 East West KCC
3,690 Feet from North South Line of Section PAT
3,690 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Phillips
Lease Name: O'Neil A Well #: 4
Date Well Completed: 7-15-1973
The plugging proposal was approved on: 9/2/2009 (Date)
by: Pat Bedore (KCC District Agent's Name)
Plugging Commenced: 10-28-2009
Plugging Completed: 10-28-2009

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|---------|---|-------|---------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| | | Surface | 8 5/8 | 215 | none |
| | | Production | 4 1/2 | 3500 | none |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforations were made at 1'710, 1'120 & 260.
Ran tubing to 3'400, spot 7sx gel, 50sx cement and 100 lbs. hulls.
Pulled tubing to 1'730, pumped 100sx cement and 200 lbs. hulls.
Pulled tubing to 500', circulated cement to surface with 40sx cement.
Pulled all tubing, pumped 25sx cement down 4 1/2 casing.
Squeezed in 35sx cement down 8 5/8 and shut in.

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 18 2009

Plugging Contractor License #: 31569 KCC DISTRICT AGENT
Name: Allied Cementing Co. Bach Oil Production
Address 1: P.O. Box 31 Address 2: _____
City: Russell State: Kansas Zip: 67665 + _____
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: Jason Bach
State of Nebraska County, Harlan, ss.
Dale Ferland Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Dale Ferland

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PAT