

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: ROADRUNNER ENERGY, INC
7225 S 85th E AVE SUITE 100
Address: TULSA, OK 74133
Phone: (918) 250-8589 Operator License #: 04555

API Number: 15-035-00360-00-01

Lease Name: Dorothy OWWO

Well Number: 4

Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): - SW - SE - NE

The plugging proposal was approved on: 11-25-08 (Date)

2756 Feet from North / South Section Line

911 Feet from East / West Section Line

by: STEVE BOND (KCC District Agent's Name)

Sec. 17 Twp. 35 S. R. 7 East West

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

County: Cowley

Producing Formation(s): List All (If needed attach another sheet)

Date Well Completed: 9-13-60

Skinner Depth to Top 2650 Bottom: 2691 T.D. 2691

Plugging Commenced: 6-2-09

Oswego Depth to Top 2504 Bottom: 2516 T.D. _____

Plugging Completed: 9-30-09

Lower Layton Depth to Top 2160 Bottom: 2174 T.D. _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Skinner	oil & wtr.	2659	2691	5 1/2"	2632'	None
Oswego	oil & wtr.	2505	2514			
Lower Layton	oil & wtr.	2166	2200			
See Page 2						

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 1900 w/3 sks. cmt on top. Shot casing at 1001. Could not pull ~~not out~~ casing. Perf. two squeeze holes at 300'. Plug well using 1" poly pipe to fill casing from bottom. Pump on 5 1/2" with 125 sks. cmt. & fill backside to surface, later pump 55 sks. with poly pipe to fill from slump. Copeland Acid & Cement Service Inc License #: 3004

Name of Plugging Contractor: _____
Address: P.O. Box 438 Haysville, LS 67060

Name of Party Responsible for Plugging Fees: Roadrunner Energy, Inc. - James D. Clay, Jr.

State of Oklahoma Tulsa, ss.

James D. Clay, Jr. (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as the same are true and correct, so help me God.

(Signature) James D. Clay
(Address) 7225 S. 85 E. Ave. Tulsa, OK 74133-3135

SUBSCRIBED and SWORN TO before me this 20th day of November, 2009

Terisa Mitchell My Commission Expires: 1-21-11
Notary Public Commission # 02020893

Mail to: KCC, Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 23 2009
CONSERVATION DIVISION
WICHITA, KS