

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: ROADRUNNER ENERGY, INC
7225 S 85th E AVE SUITE 100
Address: TULSA, OK 74133
Phone: (918) 250-8589 Operator License #: 04555
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-25-08 (Date)
by: STEVE BOND (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Miss. Lime Depth to Top: 2872 Bottom: 3020 T.D. 3020
Layton Depth to Top: 1968 Bottom: 1980 T.D. _____
Lower Layton Depth to Top: 2179 Bottom: 2216 T.D. _____

API Number: 15-035-23235-00-00
Lease Name: Dorothy
Well Number: 11
Spot Location (QQQQ): _____ - SE - SW - NE
2817 Feet from North / South Section Line
1618 Feet from East / West Section Line
Sec. 17 Twp. 35 S. R. 7 East West
County: Cowley
Date Well Completed: 4-20-83
Plugging Commenced: 7-2-09
Plugging Completed: 9-30-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Miss. Lime	wtr & S.O.	2884	2980	7"	3016	RECEIVED KANSAS CORPORATION COMMISSION NOV 23 2009 CONSERVATION DIVISION WICHITA, KS
Layton	wtr & S.O.	1970	1980			
Lower Layton	wtr & S.O.	2182	2206			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 1920' with 3 sks. cmt on top. Perf. two squeeze holes at 300'.

Plug 7" casing with coiled tubing from bottom up to surface w/ 125 sks cmt.

60/40 Poz with 4% gel. Filled 10 3/4" surface casing with cmt. from 300' to surface

After cement sank put in 10 sks. cmt. to fill to surface.

Name of Plugging Contractor: Copeland Acid & Cement Gressel License #: 3004
oilfield Service Inc
Address: P.O. Box 438 Haysville, KS 67060

Name of Party Responsible for Plugging Fees: Roadrunner Energy, Inc. - James D. Clsy, Jr. Pres.

State of Oklahoma County, Tulsa, ss.

James D. Clay, Jr. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) James D. Clay, Jr.

(Address) 7225 S. 85 E. Ave. Tulsa, Ok 74133-3135

SUBSCRIBED and SWORN TO before me this 20th day of November, 2007

Teresa Mitchell My Commission Expires: 1-21-11
Notary Public Commission # 02020893