


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Graham County, Sec 35 Twp. 10 Rge. 12 (E) (W) X
Location as "NE/CNW&SW" or footage from lines SE SE SW
Lease Owner Theodore Gore
Lease Name Zeigler Well No. B-1
Office Address Box 469 Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12-17-75 19
Plugging completed 12-22-75 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 3694' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 5 1/2" | 3672' | 538.12' |
| | | | | 8 5/8" | 168' | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3660'. Mixed and ran 5 sacks cement thru dump bailer.
Squeezed hole with 3 sacks hulls and 150 sacks 50/50 pozmix with 6% gel.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton
Southwest Casing Pulling co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Jr.
Box 364 Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 23 day of December 19 75

Sidney D. Miller
Notary Public.



12-24-75


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company: THEODORE GORE
Farm: Zeigler "B" No. 1

SEC. 35 T. 10 R. 21W
SE SE SW

Total Depth. 3680
Comm. 9-26-56 Comp. 10-5-56
Shot or Treated.
Contractor. Empire Dr'g Co.
Issued. 11-17-56

County Graham
KANSAS



CASING:
8 5/8" 175' cem w/125 sx.
5 1/2" 3672' cem w/175 sx.

Elevation. 2100 K.B.

Production. 243 BOPD

Figures indicate Bottom of Formations.

| | |
|-------------------|------|
| clay, sand, shale | 196 |
| shale, shells | 1553 |
| anhydrite | 1597 |
| shale, shells | 2110 |
| shale, lime | 2910 |
| shale, shells | 3050 |
| shale | 3195 |
| lime, shale | 3420 |
| lime | 3650 |
| lime, shale RTD | 3680 |
| Total Depth | |

Tops:
Topeka 3120
Haebner 3332
Toronto 3351
Lansing-K. C. 3368
Base Kansas City 3604
Arbuckle 3670

DST #1 3445-61 Open 1 hr. Rec. 735'
salt water. Shut in 20 mins.
BHP 1230#.

DST #2 3665-80 Open 1 hr. Weak intermittent
blow 50 mins. Shut in 20 mins.
Rec. 33' slightly oil cut mud.
BHP 500#.

RECEIVED
STATE CORPORATION COMMISSION

NOV 26 1975

CONSERVATION DIVISION
Wichita, Kansas