


15-065-02389-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

GRAHAM County. Sec. 24 Twp. 10S Rge. 21W (#) (W)  
Location as "NE/CNWxSWx" or footage from lines. APPROX. SE NE SE  
Lease Owner PETROLEUM, INC.  
Lease Name SCHMAHLFELDT Well No. 8  
Office Address ROUTE 2, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed JULY 15 19.60  
Application for plugging filed JULY 15 19.60  
Application for plugging approved JULY 15 19.60  
Plugging commenced JULY 15 19.60  
Plugging completed JULY 15 19.60  
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production NONE 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well A. D. FABRICIUS, HILL CITY, KANSAS  
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 3795 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	253'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 400' FOLLOWED BY WOODEN PLUG. PLACED 20 SACKS CEMENT THROUGH DRILL PIPE ON TOP OF PLUG. MUDDED UP WITH HEAVY MUD TO 215' FOLLOWED BY WOODEN PLUG. PLACED 20 SACKS OF CEMENT THROUGH DRILL PIPE ON TOP OF PLUG, MUDDED UP WITH HEAVY MUD TO 40' FOLLOWED BY WOODEN PLUG AND 10 SACKS OF CEMENT TO BASE OF WELL CELLAR.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 4 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor GARVEY DRILLING COMPANY  
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
DON SEARLE (employee of owner) or (#####) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle  
ROUTE 2, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 2ND day of AUGUST, 19 60  
Arthur J. Nile  
Notary Public.  
My commission expires APRIL 14, 1963



# WELL LOG

15-065-02389-0000

COMPANY PETROLEUM, INCORPORATED

SEC. 24 T.10S R. 21W

FARM SCHMAHLFELDT NO. 8

LOC. SE, NE, SE


TOTAL DEPTH 3795'

COUNTY GRAHAM CO., KANSAS

COMM. July 4, 1960 COMP. July 15, 1960

CONTRACTOR GARVEY DRILLING COMPANY

CASING 8 5/8" @ 253' w/175 sax.



ELEVATION 2185' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

40	Top soil & clay
480	Shale
1265	Shale & sand
1520	Shale
1650	Redbed
1656	Shale & red bed
1694	Anhydrite
2155	Shale & shells
2178	Shale
2605	Lime & shale
2735	Lime
2875	Lime & shale
3055	<del>XXXXX</del> Shale
3255	Lime & shale
3406	Lime
3515	Lime & shale
3570	Lime
3610	Lime & shale
3658	Lime
3730	Lime & chert
3756	Lime
3768	Conglomerate
3775	Lime & chert
3795	Arbuckle lime
3795	T. D.

RECEIVED  
STATE DEPARTMENT OF  
GEOLOGY

AUG 4 1960

CONSERVATION DIVISION  
Wichita, Kansas

State of KANSAS }  
County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #8 SCHMAHLFELDT well

Subscribed and sworn to before me this 28th day of July 19 60

My Commission Expires: April 14, 1963

Verne A. Morris  
Arthur J. Miles  
NOTARY PUBLIC