

15-065-02496-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Graham County, Sec. 24 Twp. 10 Rge. 21 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SE  
Lease Owner Petroleum, Inc.  
Lease Name Schmahlfeldt Well No. 1  
Office Address 100 Derby Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 14, 19 51  
Application for plugging filed January 14, 19 51  
Application for plugging approved January 17, 19 51  
Plugging commenced January 14, 19 51  
Plugging completed January 14, 19 51  
Reason for abandonment of well or producing formation Dry Hole



If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3760' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	180'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden plug set at 180'. Placed  $\frac{1}{4}$  sack of hulls, followed by one bucket of rock on top of plug; then 4 sacks hulls on top of rock. Cemented and displaced through drill pipe 15 sacks cement. Filled hole to 40' with heavy mud. Placed wooden plug at 40', followed by  $\frac{1}{4}$  sacks hulls, one bucket rock, and  $\frac{1}{4}$  sack hulls, in that order. Filled hole to surface with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Petroleum, Inc.  
Address 100 Derby Building, Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 25 1951  
STATE CORPORATION COMMISSION

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Eric H. Jager (employee of owner) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager  
100 Derby Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of January, 19 51

Charlotte Weidman  
Notary Public.

My commission expires October 13, 1954

PLUGGING  
JAN 24 T 10 R 21 W  
55 41

SCHMAHLFELDT WELL #1

Casing Record:-  
8-5/8" - 188'

Company - Petroleum, Inc.  
Contractor - Aylward Drig. Co.

Description:-  
SE<sub>1</sub> SE<sub>2</sub> SE<sub>3</sub> of Section  
24-108-21W, Graham  
County - Kansas.

Commenced - December 31, 1950  
Completed - January 14, 1951.

Elevation -

Production - D. & A.

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Shale and Sand	0	130	
Shale and Shells	130	190	- 8-5/8" casing set at 188'
Shale	190	735	and cemented w/ 150 Sx.
Lime and Shells	735	745	
Shale and Sand	745	800	
Shale	800	1120	
Shale and Sand	1120	1500	
Shale and Red Rock	1500	1595	
Anhydrite	1595	1631	
Shale and Shells	1631	1705	
Shale	1705	1850	
Shale and Shells	1850	2015	
Shale and Lime	2015	2405	
Lime	2405	2485	
Shale and Lime	2485	2540	
Shale	2540	2690	
Lime	2690	2730	
Lime and Shale	2730	3025	
Lime	3025	3087	
Shale	3087	3090	
Shale and Lime	3090	3195	
Lime	3195	3209	
Shale and Lime	3209	3335	
Shale and Lime	3335	3430	
Lime	3430	3623	
Lime and Shale	3623	3640	
Lime	3640	3700	
Conglomerate	3700	3730	
Shale and Lime	3730	3741	
Lime	3741	3760	

3760 - T.D.


RECEIVED  
STATE CORPORATIONS COMMISSION  
JAN 25 1951  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above drillers log, to the best of my knowledge.

*Al Skalsky*  
Al Skalsky

Subscribed and sworn to before me this 17th day of January, 1951.

*James Earl Haggue*  
Notary Public



My commission expires April 6, 1951.

PLUGGING  
FILE SEC 24 T 10 R 21W  
BOOK PAGE 55 LINE 41