

15-065-01804-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A
LEASE NAME Schneider B
WELL NUMBER 8
SPOT LOCATION SW SE SE
SEC. 35 TWP. 10S RGE. 21 (E) or (W)
COUNTY Graham
Date Well Completed 1-4-57
Plugging Commenced 2-26-85
Plugging Completed 2-26-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company
ADDRESS P. O. Box 21468 Tulsa, OK 74121-1468
PHONE # (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. 6, Hays, KS

Is ACO-1 filed? Yes If not, is well log attached? --

Producing formation Arbuckle Depth to top 3658 bottom 3675 T.D. 3675

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3658	75	8-5/8	186	-0-
				5-1/2	3666	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped 1/2 sx hulls, 9 sxs gel, and 25 sxs cmt from 3675'-3360'. Pumped 80 sxs cmt from 1100'-surf. Pumped 70 sxs cmt w/ 1/2 sx hulls behind surf csg. Well P&A'd.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568
Address P. O. Box 21468
Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Drew Tyler (employee of operator) or MAR 18 1985

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so, help me God.

(Signature) Drew Tyler

(Address) P. O. Box 21468 Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 14th day of March, 1985

Donna M. Knapp Donna M. Knapp
Notary Public



My Commission expires: 11-22-86

15-065-01804-0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Herman Geo. Kaiser, Oil Producer

SEC. 35 T. 10 R. 21#

LOC. SW SE SE

FARM Schroeder B

NO. 8

COUNTY Graham

TOTAL DEPTH 3675

COMM. 12/15/56


COMP. 12/30/56

SHOT OR TREATED

CONTRACTOR H-30, INC.

ISSUED

KANSAS



CASING

20	10	
15	8	194'
12	6	
13	5	3666'

ELEVATION 2096 K.F.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

River Sand	35
Clay & Sand Streaks	130
Blue Shale	194
Shale with Sand Streaks	1106
Shale & Red Bed	1440
Shale & Shells	1543
Anhydrite	1592
Red Bed & Shells	1625
Shale & Shells	2110
Shale & Lime Streaks	2195
Lime & Shale	3191
Lime	3255
Lime & Shale	3364
Lime	3410
Kansas City Lime	3459
Lime	3505
Kansas City Lime	3591
Lime	3630
Lime & Shale	3662
Arbuckle	3665
Lime	3675

FORMATION TOPS

HEEBNER	3326
TORONTO	3350
LANSING	3364
BASE KANSAS CITY	3594
CONGLOMERATE	3652
ARBUCKLE	3658

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1984

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By [Signature]

STATE OF KANSAS)
(SS:
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a notary public, in and for said County and State this 7th day of January, 1957.

[Signature]
Notary Public

My Commission expires February 13, 1960.