

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

File All Information Completely  
State Required Affidavit  
Must be Delivered Directly to  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217


Locate well correctly on above  
Section Plat

Rooks County, Sec. 24 Twp. 10 Rge. 20 (E) (W)  
 Location as "NE/CNW/RSW" or footage from lines SW NE NE  
 Lease Owner Southern States Oil Co.  
 Lease Name Sutor A#4 Well No.  
 Office Address Great Bend, Kansas 67530  
 Character of Well (completed as Oil, Gas or Dry Hole)  
 Date well completed 19  
 Application for plugging filed 19  
 Application for plugging approved 19  
 Plugging commenced 7/19/74 19  
 Plugging completed 7/24/74 19  
 Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey  
 Producing formation Depth to top Bottom Total Depth of Well 3749 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	164	none
				5 1/2"	3749	489'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded back to 3730' and dumped 5 sacks cement.  
 Shot pipe at 611', 550', 489', pulled 16 joints of 5 1/2" casing.  
 Allied pumped 1 sack hulls, 20 sacks gel and 135 sacks cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 19 1974

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet.)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
 Address CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE  
 NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
 CHASE, KANSAS

Subscribed and Sworn to before me this 31st day of July 1974

Margaret Melcher  
 Notary Public.



SURFACE WELL NO. 4

LOCATION: SW 1/4 NE 1/4 Sec. 20, 10-20W  
 Roske County, Kansas

OPERATOR: Birmingham-Bartlett Drilling Co.

DRILLER: Birmingham-Bartlett Drilling Co.

SURFACE CASING: Ran 9 jts. 10-3/4" 15# casing  
 cemented @ 160' with 100 sacks  
 bulk cement, 1 cc.

DEEP STRING: Ran 120 jts. 3 7/8" 15# casing  
 cemented @ 3749' with 200 sacks  
 cement.

DATE SPUNDED: 11-6-49

DATE COMPLETED: 11-18-49

TOTAL DEPTH: 3749'

100

(Figures indicate bottom of formation)

152	Clay, sand and shale
755	Shale
1145	Shale and sand
1345	Sand
1675	Shale and red bed
1675	Anhydrite
1815	Shale and shells
2275	Shale
2485	Lime and shale
2555	Lime
2570	Lime and shale
3100	Shale
3145	Lime and shale
3575	Lime
3717	Stale
3747	Chert
3749	Arbuckle

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 25 1974  
 CONSERVATION DIVISION  
 Wichita, Kansas

The undersigned Richard Hindery of the BIRMINGHAM-BARTLETT DRILLING CO. hereby certifies that the above is a true and correct log of the formations encountered in drilling the above noted well as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

BY \_\_\_\_\_

Subscribed and sworn before me  
 this 21st day of November, 1949.

Notary Public

Commission expires November 29, 1950.

*Handwritten notes:*  
 237 ft to  
 2100 ft  
 2700 ft