


15-163-12278-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks County, Sec. 24 Twp. 10 Rge. 20 (E) (W)
Location as "NE/CNW/KSWX" or footage from lines NE NW SE
Lease Owner Westrans Petroleum Company
Lease Name Leben-Sutor A#1 Well No.
Office Address Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2/8/73 19
Plugging completed 2/10/73 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Depth to top Bottom Total Depth of Well 3759 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	164	none
				5 1/2"	3757'	394'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Shot pipe at 502', 412', pulled 13 joints. Allied pumped 5 sacks hulls, 35 sacks gel and 150 sacks cement with 6% gel. Talled pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
FEB 23 1973
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor (If additional description is necessary, use BACK of this sheet) KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, SS.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of February, 1973

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

My commission expires

DRILLER'S LOG

COMPANY: LEBEN DRILLING, INC.
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: SUTOR "A" #1
 LOCATION: NE NW SE SEC. 24-10S-20W
 ROOKS COUNTY, KANSAS
 COMMENCED: 11-25-59
 COMPLETED: 12-3-59

0	70	Surface Sand and Shale
70	164	Shale
164	675	Shale and Shells
675	1180	Shale, Sand and Shale
1180	1610	Shale and Redbed
1610	1620	Anhydrite
1620	1640	Anhydrite
1640	1685	Shale
1685	2230	Shale and Lime
2230	2250	Shale and Lime
2250	2380	Lime
2380	2545	Lime
2545	2735	Lime and Shale
2735	2900	Lime and Shale
2900	3030	Lime and Shale
3030	3190	Shale and Shell
3190	3320	Lime and Shale
3320	3400	Lime
3400	3440	Lime
3440	3500	Lime
3500	3550	Lime
3550	3587	Lime
3587	3645	Lime
3645	3715	Lime
3715	3755	Lime
3755	3759	Lime
	<u>3759</u>	<u>Rotary Total Depth</u>

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 13 1972
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" surface casing @ 164' with 140 sacks Sunset cement.
 5 1/2" @ 3757 cement w/100 SX.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Sutor A #1, located in the NE NW SE of Section 24, Township 10 South, Range 20 West, Rooks County, Kansas, as reflected by the files of Leben Drilling, Inc.

Frank Hamlin

 Frank Hamlin

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS.

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 7th day of December, 1959

Juanita M. Green

 Juanita M. Green, Notary Public

My Commission Expires:
 April 23, 1963