

15-065-01829-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None
LEASE NAME Schneider A
WELL NUMBER 11
SPOT LOCATION SE SW SW
SEC. 36 TWP. 10S RGE. 21 (E or W)
COUNTY Graham
Date Well Completed 9-23-58
Plugging Commenced 1-26-85
Plugging Completed 1-28-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company
ADDRESS P. O. Box 21468 Tulsa, OK 74121-1468
PHONE # (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays, KS

Is ACO-1 filed? Yes If not, is well log attached? --

Producing formation LKC Depth to top 3431 bottom 3445 T.D. 3650

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil	3431	45	8-5/8	212	-0-
				4-1/2	3648	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. GIH w/116 jts. 2-3/8" tbq. Spot 25 sx cmt. plug from 3636'-3536'. LD 84 jts. tbq. Spot 90 sx cmt plug from 1000'-Surf. Finish LD tbq. Pump 1/2 bbl cmt on top of csg. to surf. Well P&A'd.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568
Address P. O. Box 21468 Tulsa, OK 74121-1468

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Drew Tyler (employee of operator) or FEB 08 1985
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God. CONSERVATION DIVISION
Wichita, Kansas

(Signature) Drew Tyler

(Address) P. O. Box 21468 Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 6th day of February, 19 85


Sue Mills Notary Public Sue Mills

My Commission expires: 10-4-87

COMPANY **Herman Geo. Kaiser, Oil Producer**
 FARM **Schneider "A"** NO. **11**

SEC. **36** T. **10** R. **21**
 LOC. **SE SW SW 1/4**

TOTAL DEPTH **3650'**
 COMM. **9/11/58** COMP. **9/23/58**
 SHOT OR TREATED
 CONTRACTOR **H 30, Inc.**
 ISSUED



CASINO

20	10
15	8
12	6
13	5
	4 1/2 @ 3648'

2099 K.B.
 ELEVATION **2087 D.F.**
 PRODUCTION

FIGURED INDICATE BOTTOM OF FORMATIONS

Surface soil & sand	80'
Shale	212'
Shale & Shells	645'
Shale with sand stks	800'
Shale & Shells	1110'
Sand	1280'
Shale & Shells & Red bed	1510'
Shale & Shells	1532'
Anhydrate	1571'
Shale & Shells	2280'
Shale with lime stks	2350'
Lime & Shale	3320'
Lime	3374'
Kans City Lime	3400'
Lime	3448'
Kans City Lime	3475'
Lime	3522'
Lime & Shale	3564'
Kansas City Lime	3603'
Lime	3650'

Formation Tops:

Heebner	3317'
Toronto	3338'
K.C. Lansing	3354'
Base K.C.	3585'
Conglomerate	3632'
Arbuckle	3646'

REGISTERED
 STATE COMMISSIONER OF MINES

DEC 14 1958

I hereby certify that this is a true and correct log of the
 above described well as shown by the drilling reports.
 CONSERVATION DIVISION
 WICHITA, KANSAS

H-30, Inc.
 By *[Signature]*

STATE OF KANSAS
 COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for
 said County and State this 26 of September 1958

[Signature]
 Notary Public

My Commission Expires February 13, 1960