

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-20,795-0000

LEASE NAME Stites "P"

WELL NUMBER 1

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 3 TWP. 10 RGE. 22W(E) or (W)

COUNTY Graham

Date Well Completed 12-75

Plugging Commenced 5-27-93

Plugging Completed 6-1-93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000

PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 20, 1993 (date)

by Dennis Hammel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation L/KC Depth to Top 3569' Bottom 3744 T.D. 3840

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	184	-0-
				4 1/2	3823	740'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Pump 125 sxs 60/40 poz. Displaced to 2235'. Shot csg off at 740'. Pulled csg to 612'. Pumped 30 sxs cement w/50# hulls. Pulled csg up to 128'. Spotted 35 sxs cmt w/50# hulls. Pulled remainder of csg out. Filled 8 5/8" csg w/5 sxs cmt. Total cmt 195 sxs 60/40 poz, 8% gel, with 250# hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ritchie Exploration, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 125 N. Market, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 29th day of JUNE 1993

RECEIVED 3  
STATE CORPORATION COMMISSION

[Signature]  
Notary Public

My Commission Expires:

LISA THIMMESCH  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 3-29-95

06-30-93  
CONSERVATION DIVISION  
Wichita, Kansas CP-4  
Revised 05-88