

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-005-01815-0000  
API NUMBER 15-N/A  
LEASE NAME Trico West Unit  
WELL NUMBER 107

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to  
Cons. Div. Office within  
30 days.

1650 Ft. from S Section Line  
990 Ft. from E Section Line  
SEC. 36 TWP. 10SRGE. 21 (X) or (W)  
COUNTY Graham  
Date Well Completed 12/28/55  
Plugging Commenced 10/25/94  
Plugging Completed 10/25/94

LEASE OPERATOR OXY USA Inc.  
ADDRESS P. O. Box 26100  
PHONE# (405) 749-2309 Operators License #5447

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/11/94 (date)  
by Herb Dienes (KCC District Agent's name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation LSG-KC/ARBUCKL Depth to Top 3552/3699 Bottom 3558/3705 T.D. 3705

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
Formation	Content	From	To	Size	Put in	Pulled Out
LSG-KC	OIL	3552	3558	8 5/8"	240'	
ARBUCKLE	OIL	3699	3705	5 1/2"	3699'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

RIH w 2/7/8 tbq to 3531'. Mix & xpot 75sks 60/40 POZ w/10% gel & 200# Cotton Seed Hulls. Pull tbq to 2316'. Mix & spot 75 sks 60/40 POZ w/10% gel & 200# Cotton Seed Hulls. Pull tbq to 1094' Mix & circ 40 sks 60/40 POZ w/10% gel & 100# Cotton Seed hulls. POOH w/ rest of tbq. Swedge 5 1/2" csg, mix & pump 75 sks 60/40 POZ w/105 gel. Press 5 1/2" to 500# PSI.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Co. Inc License No. 30606

Address E. Hwy 24, Box 130, Hill City, KS 67642

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.


Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 1<sup>st</sup> day of November, 19 94

Kay Ann Filmer  
Notary Public

My Commission Expires: 5-2-98



# WELL RECORD

Company Cities Service Oil Co. Well No. 7 Farm Fondoble  
 Location 990' South and 990' West of E/4 Cor. Sec. 36 T. 10 R. 21W  
 Elevation 2138 (2135 Gr.) County Graham State Kansas  
 Drlg. Comm. December 8, 1955 Contractor Lohman-Johnson Drlg. Co., Inc.  
 Drlg. Comp. December 28, 1955 Acid 500 gals. 12-29-55  
 T. D. 3705' Initial Prod. Physical Potential: 248 oil, no water, 24 hrs. (1-19-56)

**CASING RECORD:**

3-5/8" @ 240' cem. 175 sx cement  
 5-1/2" @ 3699' cem. 175 sx cement

DV-tool at 1608' with 400 sx cement and 200 cu. ft. Stratacrete.

**FORMATION RECORD:**

sand & shale	0-240
shale	340
shale, shells & red bed	1355
shale & shells	1590
anhydrite	1625
lime & shale	2200
shale & lime	2410
lime & shale	2545
shale	2690
shale & lime	2820
lime	2945
lime & shale	3050
shale & lime	3158
lime	3298
lime & shale	3361
lime	3635
lime & shale	3694
lime	3701
lime	3701 RTD = 3699 SLH
	3705 T. D.

Corr. Topoka	3151'
Corr. Heebaer	3256'
Corr. Dodge	3378'
Corr. Lansing	3393'
Corr. Base Kansas City	3636'
Corr. Conglomerate	3660'
Corr. Bros. Simpson	3681'
Corr. Arbuckle	3698'
Penetration	7'
Total Depth	3705'

Fillups: 142' oil in 1 hr.  
 405' oil in 2 hrs.  
 609' oil in 3 hrs.  
 2275' oil in 16 hrs.

SLOPE TESTS (SYFO):

500'	0°
1000'	1°
1500'	1°
2000'	0°
2500'	1°
3000'	1°

7-7/8" rotary hole.

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 11 1954  
 CONSERVATION DIVISION  
 WICHITA, KANSAS