


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 36 Twp. 10 Rge. 21 (E) (W)
Location as "NE/CNW/SW" or footage from lines Center SW/4 NW/4 S/2 SW NW
Lease Owner Harry Gore
Lease Name C. V. Lewis Well No. 3
Office Address 400 Brown Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 23 19 54
Application for plugging filed July 23 19 54
Application for plugging approved July 23 19 54
Plugging commenced July 23 19 54
Plugging completed July 23 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3825 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	188 1/2'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged with mud 3825' to 185', plug and 1/2 sack hulls 185'; 15 sacks cement 185' to 140'; mud 140' to 40', plug and 1/2 sack hulls at 40'; 10 sacks cement 40' to bottom cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Veeder Supply and Development Co.
Address P. O. Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
Floyd W. Hild (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Floyd W. Hild
Cherryvale, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of July, 19 54

My commission expires July 11, 1956

Cleo Lawson
Notary Public.

24-7366-S 3-53-20M



07-28-54

15-065-02379-0000

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Harry Gore Farm C.V. Lewis No. 3 Depth 3825'
 Contractor Veeder Supply & Dev'l Co. Pipe 188 1/2" 8 5/8" csg. cemented w/125 sacks cement
 Location Center SW/4 NW/4 Sec. 36 Twp. 10 Range 21
 Commenced 7-13-1954 Completed 7-23-1954 County Graham State Kansas

Sand, shale	0	70	70	TOPS:	
Chalk	70	125	55	Topeka	3152
Blue shale	125	360	235	Heebner	3360
Sand, shale	360	1300	940	Toronto	3384
Red Bed, shale	1300	1580	280	Lansing	3400
Anhydrite	1580	1628	48	Base KC	3628
Shale, lime	1628	3270	1642	Conglomerate	3660
Lime	3270	3685	415	Arbuckle	3789
Cherty Conglomerate	3685	3825	140		
Total Depth	3825				

Dry and plugged

AFFIDAVIT

STATE OF KANSAS)
Montgomery County) SS

Floyd W. Hild, of lawful age, being duly and solemnly sworn on oath, deposes and says:

THAT he is a resident of Cherryvale, Montgomery County, Kansas; that he knows and on oath hereby states that the above drilling log covering the Lewis #3 Well located in Section 36-10-21, Graham County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By Floyd W. Hild
Floyd W. Hild

Subscribed and sworn to before me this 26th day of July, 1954.

Loles Lawson
Notary Public

My commission expires July 11, 1956.

PLUGGING
FILE SEC 36 T 10 R 21
BOOK PAGE 51 LINE 18