

15-065-03042-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham
~~Russell~~

County. Sec. 36 Twp. 10 Rge. 21 (E) W. (W)

Location as "NE/CNW%SW%" or footage from lines SE/4 SE/4 NW/4
Lease Owner Theodore Gore,
Lease Name Theodore Gore-Lewis, C.V. Well No. 6
Office Address Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed Jan. 19, 1955 19
Application for plugging filed March 12, 1957 19
Application for plugging approved March 13, 1957 19
Plugging commenced March 12, 1957
Plugging completed March 15 1957
Reason for abandonment of well or producing formation oil exhausted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3746 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	190	none
				5-1/2	3594	2968 1/2

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3746 feet to Surface feet for each plug set.

Bridging plug had been set at 3485; Hole filled with sand from 3485 to 3440; Five sacks of cement placed in hole with dump bailer; ~~XXXX~~ ~~XXXXXX~~ Casing pulled from well, and Halliburton pump trucks thereafter pumped in ten sacks of mud, followed by plug, pumped down with 105 sacks of cement.

Plugging Complete.

RECEIVED
STATE CORPORATION COMMISSION
APR 2 - 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Barnes and Sons Pipe Pulling Co.,
Address Russell, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Theodore Gore (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Theodore Gore
400 Brown Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this first day of April, 1957

Charlotte Stanley
Notary Public.



PLUGGING
FILE SEC 36 T. 10 R. 21 W.
BOOK PAGE 147 LINE 21

15-065-03042-0000

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Harry Gore Farm C. V. Lewis No. 6 Depth 3746'
 Contractor Veeder Supply & Development Co. Pipe 190' 8 5/8" csg. cemented w/125 sacks cement
 Location SE/4 SE/4 NW/4 Sec. 36 Twp. 10 Range 21
 Commenced 1-7-1955 Completed 1-19-1955 County Graham State Kansas

Elevation: 2100 KB

	0	70	70	TOPS:	
Sand, gravel, shale	0	70	70		
Gravel, yellow shale	70	110	40		
Blue shale	110	190	80	Topeka	3133
Shale and shells	190	720	530	Heebner	3339
Sand	720	785	65	Toronto	3365
Shale and shells	785	1000	215	Lansing KC	3382
Sand and shale	1000	1300	300	Base KC	3607
Shale and shells	1300	1400	100	Cherty Cong.	3656
Shale and red bed	1400	1542	142	No Arbuckle	
Anhydrite	1542	1591	49		
Shale and shells	1591	2160	569		
Shale and lime streaks	2160	2320	160	Potential: 97	
Lime and shale	2320	2785	465		
Shale and lime shells	2785	2875	90		
Shale and lime	2875	3295	420		
Lime	3295	3680	385		
Cherty lime	3680	3701	21		
Conglomerate	3701	3746	45		
Total Depth	3746				

AFFIDAVIT

STATE OF KANSAS) SS
Montgomery County)

Floyd W. Hild, of lawful age, being first duly sworn on oath, deposes and says:

That he is a resident of Cherryvale, Montgomery County, Kansas; that he knows and hereby on oath states that the above drilling log covering the C. V. Lewis #6 Well located in Section 36-10-21 Graham County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By Floyd W. Hild
Floyd W. Hild

Subscribed and sworn to before me this 21st day of January, 1955.

Oliver Lawson
Notary Public

My commission expires July 11, 1956.

RECEIVED
NOTARY PUBLIC COMMISSION

JAN 22 - 1955

COMMISSION DIVISION
Kansas

PLUGGING
FILE SEC 36 T 10 R 21W
BOOK PAGE 147 LINE 21