

15-005-01828-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None

LEASE NAME SCHNEIDER A

WELL NUMBER 9

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 36 TWP. 10S RGE. 21 XXor (W)

COUNTY Graham

Date Well Completed 9-19-55

Plugging Commenced 3-19-86

Plugging Completed 3-19-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6 Hays, KS

Is ACO-1 filed? on old form if not, is well log attached? ---

Producing Formation Arbuckle Depth to Top 3670 Bottom 3679 T.D. 3679

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3670	79	8-5/8	187	-0-
				5-1/2	3670	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
1st plug-50 SXS cement +1 SX hulls @ 3617'. 2nd plug-25 SXS hulls @ 3117'.
Pumped 18 SXS gel w/1 SX hulls to 1317'. Circ 100 SXS cement w/1 SX hulls
+1 SX cello flakes. Fill 5-1/2" w/10 SXS cement. Pump 20 SXS cement on top
of plug. Pump 90 SXS cement +1 SX hulls down annulus. JOB COMPLETE
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charlotte Van Valkenburg
(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 1st day of April, 19 86

Carol Sue Brumbaugh

My Commission Expires: 2/11/89

STATE CORPORATION COMMISSION

APR - 3 1986

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84

15-065-01828-0000

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLING BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Herman Geo. Kaiser & Francis Oil & Gas, Inc.**

SEC. **36** T. **10S** R. **21W**
 LOC. **SW SW SW**


FARM **Schneider A** NO. **9**

COUNTY **Graham**

TOTAL DEPTH **3679**
 COMM. **9/6/55**

COMP. **9/19/55**

SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED



CASING

20	10
15	8
12	6
13	5

194'
3670'

ELEVATION **2093** KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	690
Sand	770
Shale & Shells	1020
Sand	1235
Shale & Red Bed	1510
Anhydrite	1587
Red Bed, Shale & Shells	1860
Shale & Shells	2046
Shale, Shells & Salt	2175
Shale, Lime & Salt	2280
Shale & Lime	3425
Lime	3607
Lime & Shale	3660
Lime & Chert	3679

FORMATION TOPS

HEEBNER	3319
TORONTO	3311
LANSING	3358
BASE-KANSAS CITY	3591
SIMPSON SHALE	3616
SHALEY ARBUCKLE	3655
SOLID ARBUCKLE	3668

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *[Signature]*

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 22nd day of September, 1955.

[Signature]
 Notary Public

MAR 5 1956

My Commission expires February 13, 1956
 CONSERVATION DIVISION
 Wichita, Kansas