


15-065-02349-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 36 Twp. 10 Rge. (E) 21 (W)

Location as "NE/CNWxSWx" or footage from lines C E/2 SE/4 SW/4

Lease Owner Herman Geo. Kaiser, Oil Producer

Lease Name Schneider A Well No. 10

Office Address 908 Palace Bldg., Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 18, 19 56

Application for plugging filed " " 19 "

Application for plugging approved " " 19 "

Plugging commenced " " 19 "

Plugging completed " " 19 "

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3740 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	205'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded hole with heavy Rotary Mud to 180 ft.,  
set cementing plug and cemented with 1/2 sack Halls  
and 15 sacks cement. Mudded to 40 ft., set cementing  
Plug and 1/2 sack Halls and 10 sacks cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.

Address 710 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Employee of Contractor

L. G. Sponenberg of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN to before me this 20 day of April, 19 56

My commission expires February 13, 1960.

Rose Turley  
Notary Public.  
STATE CORPORATION COMMISSION

MAY 1 X 1956

CONSERVATION DIVISION  
Wichita, Kansas


**PLUGGING**  
FILE SEC 36 T 10 R 21W  
BOOK PAGE 55 LINE 7

15-065-02349 - 0000

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Herman Geo. Kaiser & Francis Oil & Gas, Inc.** SEC. **36** T. **10** R. **21W**  
FARM **Schneider A** NO. **10** LOC. **C E/2 SE SW**

TOTAL DEPTH **3740'** COUNTY **Graham**  
COMM. **4/8/56** COMP. **4/18/56** KANSAS  
SHOT OR TREATED  
CONTRACTOR **H-30, Inc.**  
ISSUED



CASING  
20 10  
15 8 **205'**  
12 6  
13 5

ELEVATION **2108 K.B.**  
PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay, Shale & Sand	125
Shale & Shells	207
Shale, Shells & Sand Streaks	695
Sand	815
Shale, Shells & Sand Streaks	1030
Sand	1240
Shale & Shells	1250
Shale, Shells & Red Bed	1540
Anhydrite	1600
Shale, Shells & Salt	2050
Shale & Lime	3665
Shale, Lime & Chert	3704
Cherty Conglomerate	3740

FORMATION TOPS

HEEBNER	3355
LANSING	3394
BASE KANSAS CITY	3622
CONGLOMERATE	3669

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *L. P. Sproung*

STATE OF KANSAS }  
                          } SS:  
COUNTY OF SEDGWICK }

Subscribed and sworn to before me, a notary public, in and for said County and State this 20th day of April, 1956.

*Rose Turey*  
Notary Public

My Commission expires February 13, 1960.

**PLUGGING**  
FILE SEC 36 T 10 R 21W  
BOOK PAGE 55 LINE 7

RECEIVED  
OBSERVATION DIVISION  
Wichita, Kansas