

15-005-03295-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A
LEASE NAME Schneider A
WELL NUMBER 1
SPOT LOCATION NE NW SW
SEC. 36 TWP. 10 SRGE. 21 ~~(N)~~ or (W)
COUNTY Graham
Date Well Completed 5-6-54
Plugging Commenced 3-6-85
Plugging Completed 3-6-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company
ADDRESS P. O. Box 21468 Tulsa, OK 74121-1468
PHONE # (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. 6, Hays, KS

Is ACO-1 filed? Yes If not, is well log attached? --

Producing formation Arbuckle Depth to top 3684 bottom 3696 T.D. 3696

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3684	96	8-5/8	255	-0-
				5-1/2	3690	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped 1 sx hulls, 10 sxs gel, and 25 sxs cmt from 3400'-3050'. Pumped 90 sxs cmt w/hulls from 1100'-surf. Pumped 60 sxs cmt behind surf csq. Well P&A'd.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568
Address P. O. Box 21468 Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Drew Tyler (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says:


I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Drew Tyler

(Address) P. O. Box 21468 Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 14th day of March, 1985

Donna M. Knapp Donna M. Knapp
Notary Public



My Commission expires: 11-22-86

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1985
CONSERVATION DIVISION
Wichita, Kansas

15-065-03295-0000

KANSAS GEOLOGICAL SOCIETY
 WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY Herman Geo. Kaiser, Oil Producer

SEC. 36 T. 10 R. 21
 LOC. NE NW SW

FARM Schneider NO. 7

TOTAL DEPTH 3696'
 COMM. 4/16/54 COMP. 4/27/54
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED

COUNTY Graham
 KANSAS



CASING
 20 10
 15 8 255'
 12 6 3690'
 13 5

ELEVATION 2123 K.B.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Sand & Course gravel	95
Shale & Sand	160
Shale	695
Sand	790
Shale	875
Shale & Shells w/ streaks of iron	1025
Sand	1345
Shale & Sand	1465
Red Bed & Shale	1565
Anhydrite	1625
Red Bed, Shale & Shells	1750
Shale & Shells	2085
Shale, Shells & Salt	2170
Shale & Lime - Brkn.	2200
Shale & Lime	3454
Lime	3466
Shale & Lime	3559
Lime	3604
Shale & Lime	3696

FORMATION TOPS (K.B. Meas.)

HEEBNER	3354
LANSING K.C.	3397
CONGLOMERATE	3668
ARBUCKLE	3685

2123
 15-65-1
 15-8

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

RECEIVED
 STATE CORPORATION COMMISSION

H-30, INC.

DEC 14 1984

CONSERVATION DIVISION
 Wichita, Kansas

By

[Signature]

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 29th day of April, 1954.

[Signature]
 Notary Public

My Commission expires February 13, 1956.