

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-00453-0000
API NUMBER None

LEASE NAME Schneider A

WELL NUMBER 2

2310 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 36 TWP. 10S RGE. 21 (S) or (W)

COUNTY Graham

Date Well Completed 5/15/54

Plugging Commenced 10/6/92

Plugging Completed 10/6/92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? On old form If not, is well log attached? -

Producing Formation Arbuckle Depth to Top 3685 Bottom 3714 T.D. 3714

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3681	3714	8 5/8	209	-0-
				5 1/2	3685	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped 275 sxs 65/35 poz w/10% gel + 500# hulls from PBTD to surface. Pumped 75 sxs poz down annulus.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 65088

Address P. O. Box 21468, Tulsa, OK 74121-1468

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 9th day of November, 19 92

Linda M. Mordock
Notary Public

My Commission Expires: 12-23-93


15-065-00453-0000

COMPANY **Herman Geo. Kaiser**
 FARM **Schneider** NO. **2**

SEC. **36** T. **10** R. **21W**
 LOC. **NW NE SW**

TOTAL DEPTH **3691**
 COMM. **4/28/54** COMP. **5/9/54**
 SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED

COUNTY **Graham**
 KANSAS



CASING		
20	10	
15	8	209'
12	6	
13	5	3685'

ELEVATION **2119 K.B.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Sand & Course Gravel	75
Sand & Shale	160
Shale	1030
Shale & Sand	1450
Red Bed & Shale	1568
Anhydrite	1620
Red Bed	1625
Red Bed & Shale	1900
Shale, Shells & Red Bed	2120
Shale & Shells	2158
Shale, Shells & Salt	2180
Shale & Lime	3691

FORMATION TOPS (K.B. Meas.)

HEEBNER	3347
TORONTO	3370
LANSING	3387
BASE KANSAS CITY	3612
CONGLOMERATE	3662
ARBUCKLE	3681

I hereby certify that this is a true and correct copy of the above described well as shown by the drilling reports.

RECEIVED
 CORPORATION COMMISSION
 SEP 21 1954
 H-30, INC. CONSERVATION DIVISION
 Wichita, Kansas
 By *R. C. Sperry*

STATE OF KANSAS
 COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 12th day of May, 1954.

Rose Lucey
 Notary Public

My Commission expires February 13, 1956.