



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RCUD
12-06-66

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Melvin Simpson of Murray & Simpson, Inc., has this date requested permission to plug the following described well:

Mr. Simpson guarantees payment of the plugging fee.

Operator's full Name: C & E Oil Company
c/o Murray-Simpson, Inc.,
Complete Address: Box #405, Great Bend, Kansas.

Lease Name: McIntire Well No. 2

Location: NE-NE-SE Sec. 10 Twp. 10 Rge. (E)(W) 21

County Graham Total Depth 3781 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Simpson was instructed to plug the well as follows:

260'--8 5/8" Surface pipe, cement circulated.
3761'--4 1/2" Production casing cemented with plug stopped @
3730', no amount of cement indicated. Drilled out cement and
found well to have been originally drilled 28' deeper than
reported. Well abandoned.

Sand well back to 3700' and set 3 Sx. cement with dump bailer.
Pull 4 1/2" to 550' and displace 20 Sx. cement thru 4 1/2". pull 4 1/2"
to 250' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2" set rock
bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent