

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

APR 27 1967

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply has this date requested permission to plug the following described well:

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Union Texas Petroleum,

Complete Address: Suite B-400, 1740 Broadway, Denver, Colorado.

Lease Name: Bartos Well No. 3

Location: NW-NW-NE Sec. 10 Twp. 10 Rge. (E)(W) 21

County Graham Total Depth 3842 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bailey was instructed to plug the well as follows:

259' -- 8 5/8" Surface pipe, cement circulated with 175 Sx.
3842' -- 5 1/2" Production casing cemented with 125 Sx. Well
plugged back to 3800'. Top perforations @ 3652'.

Push plug to 3600', sand back to 3575' and set 5 Sx. cement
with dump bailer. Pull 5 1/2" casing and squeeze well with 50
Sx. gel with 10 Sx. hulls in initial gel to encounter pressure
and follow with 75 Sx. cement.

Very truly yours,

H. L. Nichols
Conservation Division Agent