



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. A. J. Nelson of Leben Drilling, Incorporated has this
date requested permission to plug the following described well:

Mr. Nelson guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling, Incorporated,

Complete Address: Box #486, Great Bend, Kansas.

Lease Name: Beiker Well No. 5

Location: NE-SE-SE Sec. 12 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3824' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Nelson was instructed to plug the well as follows:

??--8 5/8" Surface pipe evidently circulated. (No Record).
3814'--5 1/2" Production casing cemented on bottom. open hole completion.
5 1/2" had been squeezed thru perforations from anhydrite to surface. Plug
had been set @ 3550' with no indication of any perforations above.

Squeeze 5 1/2" casing with 1 sack hulls, 90 Sx. cement and 25 sacks gel,
staged.

Very truly yours,

N. L. Nichols

Conservation Division Agent