

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Edwin Eckman of John O Farmer has this date requested permission to plug the following described well:

Operator's Full Name: John O Farmer

Complete Address: Russell, Kansas

Lease Name: McCellan Well No. 4

Location: NW-SE-SE Sec. 2 Twp. 10 Rge. 21 (E)  (W)

County: Shannon Total Depth: 3828'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Eckman was instructed to plug the well as follows:

8 5/8" @ 165' w/100 cv 5 1/2" @ 3824' w/100 cv 4' open hole - Squeezed @ 1275' w/150 cv (1956) - Squeezed @ 1053' w/200 cv (1965) Ordered 325 cv 50/50 permix 6% gel 3% cc + 12 hulls. Pump in 50 cm + 1 hull -> 25 gel -> 125 cm + 3 hulls - P.S.I. Max 1800 - Shut in 350 psi Pump in 8 5/8" 75 cm + 3 hulls - PSI Max 600 - Shut in 300 psi

Very truly yours,

\_\_\_\_\_  
Conservation Division Agent