

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 P. Meridian
WICHITA, KANSAS STATE CORPORATION COMMISSION

RECEIVED
MAR 23 1973
3-23-1973
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Izadore Dreher of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Dreher guarantees payment of the plugging fee.

Operator's full Name: John O Farmer, Incorporated,

Complete Address: 370 West Wichita Avenue, Russell, Kansas.

Lease Name: McClelland Well No. 5

Location: SE-SE-SE Sec. 2 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 4014' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Dreher was instructed to plug the well as follows:

165'--8 5/8" Surface casing, cement circulated with 100 Sx.

3832'--5 1/2" casing cemented on bottom. 5 1/2" casing has been squeezed @ 1200'.

Squeeze 5 1/2" casing with 1 sack hulls, 30 sacks gel and 150 Cu. Ft. cement, staged. Squeeze annulus with 150 Cu. Ft. cement.

Very truly yours,

W. L. Nichols
Conservation Division Agent