

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67227

RECEIVED
STATE CORPORATION COMMISSION
2-12-1973
FEB 12 1973
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co., Inc has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company,

Complete Address: Box #287, Great Bend, Kansas.

Lease Name: Noah Well No. 5

Location: NW-SW-NW Sec. 2 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3840' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

1809'--8 5/8" Surface casing, cement circulated with 1000 Sx.

3823'--5 1/2" Production casing cemented on bottom with 200 Sx. Top perforations @ 3510'.

Sand well back to 3500' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing. Check fluid level and if below 1000' set wood and rock bridge on top of fluid and fill well with Redi-Mix cement.

Very truly yours,

M. L. Nichols
Conservation Division Agent