

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 26 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Victor Gustus of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Gustus guarantees payment of the plugging fee.

Operator's full Name: Bankoff & Leben,

Complete Address: 815 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Rudman Well No. 1

Location: NE-NE-SE Sec. 5 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3524 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gustus was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 690'.

Circulate hole with heavy mud. Pull DP to 900' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.
Pull DP, set plug @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

A. L. Nichols
 Conservation Division Agent