

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 4-4-1969
 APR 4 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co., Inc. has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company,

Complete Address: Box # 287, Great Bend, Kansas.

Lease Name: Noah Well No. 1

Location: NW-NW-NW Sec. 2 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3870' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

1789'--8 5/8" Surface casing, cement circulated with 1050 Sx.
3820'--5 1/2" Production casing cemented on bottom with 200 Sx. Well
plugged back to 3770'. Top of perforations @ 3494'.

Push plug to 3450', sand back to 3400' and set 5 Sx. cement with dump
bailer. Pull 5 1/2" casing and squeeze well with 35 sacks gel and 60 Sx.
cement.

Very truly yours,

M. L. Fiedler
 Conservation Division Agent