

Operator Name: John O. Farmer, Inc. Lease Name: Van Loenen "B" Well #: 1
 Sec. 31 Twp. 7 S. R. 21 East West County: Graham

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)
 Samples Sent to Geological Survey Yes No
 Cores Taken Yes No
 Electric Log Run Yes No
 (Submit Copy)

List All E. Logs Run:

Dual Compensated Porosity Log, Dual Induction Log, Microresistivity Log, Dual Receiver Cement Bond Log

<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample
Name	Top	Datum
Anhydrite	1763'	(+413)
Topeka	3144'	(-968)
Heebner	3350'	(-1174)
Toronto	3372'	(-1196)
Lansing/KC	3386'	(-1210)
Base/KC	3583'	(-1407)
Conglomerate Sand	3665'	(-1489)
Arbuckle	3674'	(-1498)

CASING RECORD <input checked="" type="checkbox"/> New <input checked="" type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	23#	221'	Common	160	3% C.C., 2% gel
Production	7-7/8"	5-1/2"	14#	3738'	EA-2	160	
Port Collar				1768'	60/40 Pozmix	450	1/4# floseal/sk.

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
___ Perforate				
___ Protect Casing				
___ Plug Back TD				
___ Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4 SPF	3683-92' (Arbuckle)	500 gals. 15% NE-FE	

TUBING RECORD		Size	Set At	Packer At	Liner Run
		2-7/8"	3698'		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr.			Producing Method		
10-18-07			<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	5.00		0.00		19.0°

Disposition of Gas Vented Sold Used on Lease (If vented, Submit ACO-18.)

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify)

Production Interval 3683-92'

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

COPY No. 1598

Date	9-20-07	Sec.	31	Twp.	7	Range	21	Called Out		On Location		Job Start		Finish	12:15 PM
Lease	Van Loenen			Well No.	1			Location	R-18 + Hwy 24 W			County	Gr	State	Re
Contractor	WWD Drilling Rig 8							Owner	W W						
Type Job	Surface							To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.							
Hole Size	12 1/4			T.D.	222			Charge To	J.O. Farmer, Inc.						
Csg.	8 5/8 236			Depth	221			Street							
Tbg. Size				Depth				City	State						
Drill Pipe				Depth				The above was done to satisfaction and supervision of owner agent or contractor.							
Tool				Depth											
Cement Left in Csg.	10-15'			Shoe Joint				<p style="text-align: right;">CONFIDENTIAL DEC 21 2007 KCC</p>							
Press Max.				Minimum											
Meas Line				Displace	13 Bbl										
Perf.							CEMENT								

EQUIPMENT				Amount Ordered	160 Com 3% CC 2% level		
Pumptrk	1	No.	Cementer	Steve	Consisting of		
			Helper				
Bulktrk	2	No.	Driver	Dave F	Common		
			Driver				
Bulktrk		No.	Driver	Brandon	Poz. Mix		
			Driver				

JOB SERVICES & REMARKS				Gel.	
Pumptrk Charge				Chloride	
Mileage				Hulls	
Footage				Salt	
			Total	Flowseal	

Remarks: Cement did Circulate

				Sales Tax	
				Handling	
				Mileage	
				Sub Total	
				Total	
				Floating Equipment & Plugs	
				Squeeze Manifold	
				Rotating Head	
				Tax	
				Discount	
				Total Charge	

Handwritten signatures and initials

RECEIVED
KANSAS CORPORATION COM
DEC 26 2007
CONSERVATION DIVIS
WICHITA, KS

X
Signature

JOB LOG

SWIFT Services, Inc. COPY

DATE 9-26-07 PAGE NO. 1

CUSTOMER John O. Farmer WELL NO. 1 LEASE VAN LOREN "B" JOB TYPE Cement LS TICKET NO. 12689

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1745							On location w/ Float Eq. Rig L-D D.P.
	1840							Rig Fin L-D D.P.
	1940							Start 5 1/2" Casing - Insert Float Shoe, Latch Down Baffle - 1st collar -
								Cent. 1, 3, 6, 8, 11, 14, 61
								Cement Baskets - 2, 13, 60, Number 50
								Port collar @ 1772' - 5" link hole - Number 51
	2135							Fin running casing - Hookup to circ.
	2145							Start circ & Rotating pipe
	2210							Fin circ casing.
	2212		3					Plug RH-15 SKS
	2215	4	12				200	Pump 500 gal Mudflush
		5	20				200	Pump 20 BBL KCL flush
		4 1/2					200	Start mixing 160 SKS EA-2 cut
	2238	4 1/2	39				100	Fin mixing cut.
								Wash out Pump & Lines
								Release Latch down Plug,
	2242	8					700	Start Displ. - Rotate casing
							200	Psi slowly incr
			60				300	Caught cut lift
			75				600	Stop Rotating
							800	Final lift press
	2255		91				1600	Plug down - Held
								Release Psi & Held
	2300							Job Complete

CONFIDENTIAL
DEC 21 2007
KCC

Thanks
Don, Blaine & Ryan

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 26 2007
CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., INC.

24708

COPY

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>10-15-07</u>	SEC. <u>31</u>	TWP. <u>7S</u>	RANGE <u>21W</u>	CALLED OUT	ON LOCATION	JOB START <u>2:00pm</u>	JOB FINISH <u>2:30p.m.</u>
LEASE <u>UAV WENEN</u>	WELL # <u>B-1</u>	LOCATION <u>Bogue #24 1N R25 1W R350</u>			COUNTY <u>Graham</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>NEW</u>		<u>1N winto</u>					

CONTRACTOR Poe

TYPE OF JOB Part Cellar

HOLE SIZE _____ T.D. _____

CASING SIZE 5/2 DEPTH _____

TUBING SIZE 2 7/8 DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL Expert DEPTH 1768

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

EQUIPMENT

PUMP TRUCK CEMENTER Craig

409 HELPER Adrian

BULK TRUCK _____

396 DRIVER Chris B.

BULK TRUCK _____

_____ DRIVER _____

REMARKS:

Plug set @ 3512

Spot Sand 3447 = 176L

Part Cellar 1768 = 814BL Displaced!

Cement Circulate? Part 15 wash clean!

Run down & wash sand off plug

Thanks!

OWNER _____

CEMENT AMOUNT ORDERED 450 60/40 60/60

14 # 20

2 Sand

COMMON	<u>270</u>	@	<u>11.10</u>	<u>2992.00</u>
POZMIX	<u>180</u>	@	<u>6.20</u>	<u>1116.00</u>
GEL	<u>27</u>	@	<u>16.65</u>	<u>449.55</u>
CHLORIDE		@		
ASC		@		
	<u>FloSral 113165</u>	@	<u>2.0016</u>	<u>226.00</u>
	<u>Sand 2</u>	@	<u>10.50</u>	<u>21.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>4795</u>	@	<u>1.90</u>	<u>910.10</u>
MILEAGE	<u>109/54/mile</u>			<u>3017.70</u>
TOTAL				<u>8737.35</u>

CONFIDENTIAL
DEC 21 2007
KCC

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 955.00

EXTRA FOOTAGE @ _____

MILEAGE 70 @ 6.00 420

MANIFOLD @ _____

@ _____

@ _____

TOTAL 1375.00

PLUG & FLOAT EQUIPMENT

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
TOTAL _____		

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

CHARGE TO: JD Farmer

STREET _____

CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Susan K. Eckman

PRINTED NAME _____

RECEIVED
KANSAS CORPORATION COM

DEC 26 2007

CONSERVATION DIVISION
WICHITA, KS