

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company,
Complete Address Box #553, Russell, Kansas.
Lease Name Schneider Well No. A-6
Location CSW-SE-SW Sec. 31 Twp. 10 Rge. (E) (W) 20
County Rooks Total Depth 3668'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Halliburton Services,
Address Box #296, Hill City, Kansas. License No. _____
Operation Completed: Hour 1:15 PM Day 15 Month 6 Year 1971

The above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated with 175 Sx.
3654'--5 1/2" Production casing cemented on bottom with 175 Sx. Stage collar set @
1535' and cement circulated to surface.
Squeezed 5 1/2" casing initially with 1 sack hulls and 20 Sx. cement from 3668' to 3550',
followed with 28 sacks gel from 3550' to 750' and finally 95 Sx. cement from 750' to
bottom of cellar. Maximum pump-in pressure-450#. Final shut-in pressure-100#.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Pichak
Well Plugging Supervisor

INVOICED

DATE 6/22/71
INV. NO. 3894 W.