

15-163-03264-0000

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 121-25

LOCATION NE NW NW

SEC. 51 TWP 10 RGE. 20

Dry Hole RT KCC Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Schneider

Operator Magnolia Pet Company Address Box 770 Great Bend,

Field _____ County Rooks

Total Depth 3749 Feet.

Plugging Contractor Jayhawk Pipe Pulling

Plugging Contractor's License No. 19

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 250' circulated with cement - 5 1/2" at 3748' with
200 sax cement behind. Lane Wells plugs to 3515' perforated
3504'.

Filled with sand to 3490', set 4 sax cement with dump bailer,
pulled 2350' 5 1/2", filled with mud to 245', set rock and 15
sax cement, mud to 35', set rock and 10 sax cement to bottom
cellar.

[Signature]
District Conservation Agent

Date 8-20-53

PLUGGING
FILE SEC 31 TWP 10 R 20
BOOK PAGE 121 LINE 25

RECEIVED
STATE CORPORATION COMMISSION
8-22-53