

15-163-20290-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum, Inc.

Complete Address 300 W. Douglas Wichita, Kansas 67202

Lease Name Keller "C" Well No. 1

Location SW NW SE Sec. 36 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3735

Abandoned Oil Well Gas Well Input Well SWD Well D & A XXX

Other well as hereafter indicated

Plugging Contractor Garvey Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 6P Day 2 Month 2 Year 1970

The above well was plugged as follows:

RTD 3735' 8 5/8 csg set at 215' cwc 185 sk. Cmt. Mat. 50-50 poz cmt 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Messing
Well Plugging Supervisor

INVOICED

DATE 2/6/70
INV. NO. 1370-W