

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

R

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 152-25 County: Rooks

Location: SE SE SW Sec. 36 Twp. 10 Rge. 20 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3706

I have this date completed supervision of plugging of:

Lease Name: Keller Well No. 1

Operator's Full Name: Francis Oil & Gas

Complete Address: 905 Palace Bldg Tulsa, Okla

Plugging Contractor: Ace Pipe Pulling Co & Globe Cementing Co

Address: Great Bend, Kans License No. 2

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes  No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 2PM Day 9 Month 10 Year 58

The above well was plugged as follows:

8 5/8" at 225' circulated with cement.

Pulled 2810' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2"

( Gel mud ), displaced 20 sax cement through 5 1/2" at 550', heavy mud to

180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to

35', set rock and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 36 T. 10 R. 20W  
BOOK PAGE 132 LINE 25

RECEIVED  
STATE CORPORATION COMMISSION

OCT 21 1958  
CONSERVATION DIVISION  
Wichita, Kansas

15-163-19147-0000

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Artnell Company,

Drilled for ~~Veeder Supply & Dev'l. Co. et al~~ Farm Carl Keller No. 1 Depth 3706'  
 Contractor ~~Veeder Supply & Dev'l. Co.~~ Pipe 225' 8 5/8" cas. w/140 sacks  
3700' 5 1/2" cas. w/150 sacks  
 Location S1/4, S2/4, S3/4 Sec. 36 Twp 10S Range 20W  
 Commenced 1-27-1957 Completed 5-8-1957 County Rooks State Kansas

Soil, sand, shale	0	45	45	Elevations Gr. 2102 Dr. 2105
Grey shale	45	105	60	
Blue shale	105	225	120	
Shale	225	670	445	
Shale, sand	670	990	320	
Sand, shale	990	1220	230	
Shale	1220	1245	25	
Shale, red bed	1245	1520	275	
Anhydrite	1520	1560	40	
Shale and shells	1560	2040	480	
Shale, lime streaks	2040	2125	85	
Shale, lime	2125	2235	110	
Lime and shale	2235	2645	410	
Shale and lime streaks	2645	2760	115	
Lime and shale streaks	2760	2840	80	
Lime, shale	2840	3207	367	
Lime	3207	3485	278	
Lime cherty	3485	3552	67	
Lime	3552	3685	133	
Cong. Simpson	3685	3697	12	
Arbuckle	3697	3706	9	
T. D.	3706			

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 27 1957  
 CONSERVATION DIVISION  
 Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS )  
 Montgomery County) SS

C. H. Woods, of lawful age, being first duly sworn on oath, deposes and says:

THAT he has read the above drilling log covering the Carl Keller #1 well located in Section 36-10S-20W, Rooks County, Kansas, and that the same is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By C. H. Woods

Subscribed and sworn to before me this 10th day of May, 1957.

Notary Public

My commission expires July 11, 1960.

PLUGGING  
 FILE SEC. 36 T. 10 R. 20W  
 BOOK PAGE 132 LINE 25