

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20786-00-00
Spot: NESW Sec/Twnshp/Rge: 5-19S-4E
1320 feet from S Section Line, 1320 feet from W Section Line
Lease Name: OBORNY Well #: 1
County: MARION Total Vertical Depth: 2422 feet

Operator License No.: 30483
Op Name: KREMEIER, LES DBA KREMEIER PROD
Address: 3183 US HWY 56
HERINGTON, KS 67449

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		150 SX CMT
PROD	4.5	2421		50 SX CMT 78.72

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/29/2009 10:00 AM
Plug Co. License No.: 30483 Plug Co. Name: KREMEIER, LES DBA KREMEIER PROD. AND OPER. CO.
Proposal Rcvd. from: LES KREMEIER Company: KREMEIER PRODUCTION & OPER Phone: (785) 258-2321

Proposed Plugging Method: PUMP 35 SXS CEMENT AT BOTTOM. CUT CASING AND PULL TO 300' AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: GREG EVES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/29/2009 3:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

RUN TUBING TO 2376' AND PUMPED (2SXS CALCIUM CHLORIDE) W 35 SXS CEMENT. CUT CASING AT 1610 FEET AND PULLED. RUN TUBING TO 300' AND PUMPED 175 SXS CEMENT TO CIRCULATE TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2400	2410	CSG	

INVOICED
DATE 12.29.09
INV. NO. 2010060640

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 19 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED TICKET #23122 TOTAL = 210 SXS 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed Greg Eves
(TECHNICIAN)

Form CP-2/3

* PLUGGED DUE TO COMPLIANCE REASONS. ABA OVER 10 YR

✓SK