

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21355-00-00
Spot: SENE Sec/Twnshp/Rge: 23-20S-16W
4290 feet from S Section Line, 330 feet from E Section Line
Lease Name: NELSON A Well #: 3
County: PAWNEE Total Vertical Depth: 3860 feet

Operator License No.: 30737
Op Name: YOST, M.A. OPERATIONS, INC
Address: 611 S FOSSILL PO BOX 811
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1068		WITH 400 SX CMT
PROD	5.5	3860	2210	WITH 175 SX CMT

125.45

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2009 11:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3740' & 5 SX CMT. PLUG AT 1090' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2009 1:31 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3700' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1090' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3795	3798		

INVOICED
DATE 12-29-09
INV. NO. 2010060614

RECEIVED
NOV 06 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
NOV - 2 2009
KCC DODGE CITY