

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12555-00-00
Spot: S2SENW Sec/Twnshp/Rge: 20-22S-11W
2970 feet from S Section Line, 3300 feet from E Section Line
Lease Name: AIKEN Well #: 1
County: STAFFORD Total Vertical Depth: 3604 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	190		WITH 150 SX CMT
PROD	5.5	3577	1640	WITH 75 SX CMT

117.13

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/23/2009 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 3490' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 220' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/23/2009 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3490' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 220' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3576	3603		OH
3553	3556		
3543	3548		

INVOICED
DATE 12-29-09
INV. NO. 2010060618
RECEIVED
NOV 06 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 5% GEL BY QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 01

RECEIVED
OCT 30 2009
KCC DODGE CITY

Signed Stephen J Pfeifer
(TECHNICIAN)