

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-20845-00-00
Spot: SESESE Sec/Twnshp/Rge: 35-23S-21E
60 feet from S Section Line, 440 feet from E Section Line
Lease Name: CLYDE STEWART Well #: 4-80
County: BOURBON Total Vertical Depth: 722 feet

Operator License No.: 3728
Op Name: KENT, ROGER DBA R J ENTERPRISES
Address: 22082 NE NEOSHO RD
GARNETT, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.25	20	0	
PROD 2		722	0	

35.00

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/17/2009 8:00 AM
Plug Co. License No.: 3728 Plug Co. Name: KENT, ROGER DBA R J ENTERPRISES
Proposal Rcvd. from: ROGER KENT Company: KENT, ROGER DBA R J ENTERPRIS Phone: (785) 448-6996

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO 722' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 07/17/2009 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 700'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 24 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED
KCC DISTRICT #3

NOV 10 2009 CPT

CHANUTE, KS

RECEIVED
NOV 12 2009
KCC WICHITA

INVOICED

DATE 12-29-09

INV. NO. 2010060612

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel
(TECHNICIAN)

PKA