

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-22726-00-02  
Spot: SWNWSW Sec/Twnshp/Rge: 16-35S-7E  
1340 feet from S Section Line, 4804 feet from E Section Line  
Lease Name: DOROTHY Well #: 7  
County: COWLEY Total Vertical Depth: 2928 feet

Operator License No.: 4555  
Op Name: ROADRUNNER ENERGY, INC.  
Address: 7225 S 85 E AVE # 100  
TULSA, OK 74133

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2755		
SURF	8.625	148		75 SX <u>95.16</u>
PROD	5.5	2910		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/24/2009 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.  
Proposal Rcvd. from: DENNIS CLAY Company: ROADRUNNER ENERGY Phone: (918) 250-8589

Proposed Plugging Method: AS PER KCC RULES & REGS, SET CIBP @ 1985', W/3 SXS, PERFORATE @ 300', CIRCULATE CEMENT TO SURFACE

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/28/2009 1:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

8-24-2009, RIH ON WIRELINE SET CIBP @ 1980', DUMP BAILED 3 SXS CEMENT ON TOP. PERFORATED SQUEEZE HOLES @ 350'. 9-30-2009, RIH W/1" TBS @ 360', COPELAND ACID & CEMENT MIXED & PUMPED 95 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN 1" TBG, SWEDGED INTO 5.5" CASING. FINISHED PUMPING 31 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. COPELAND ACID & CEMENT, TICKET #34284. 10-1-2009, TAGGED CEMENT INSIDE 5-1/2" CASING @ 250', OUTSIDE 5-1/2" CEMENT @ SURFACE. 10-28-2009, RIH W/TBG @ 245', COPELAND ACID & CEMENT MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P.A. COMPLETE 1:30 P.M. 10-28-2009. CEMENT TICKET #34296. TOTAL 161 SXS ON TOP PLUG.

Perfs:

Top	Bot	Thru	Comments
2036	2042	CSG	

RECEIVED  
NOV 13 2009  
KCC WICHITA

INVOICED  
DATE 12-29-09  
INV. NO. 2010060613

Remarks: CIBP SET @ 2755'

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)