

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-21074-00-00  
Spot: SWNESESW Sec/Twnshp/Rge: 31-31S-39W  
696 feet from S Section Line, 3169 feet from E Section Line  
Lease Name: MILBURN A Well #: 2  
County: MORTON Total Vertical Depth: 6001 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

| String | Size  | Depth (ft) | Pulled (ft) | Comments                  |
|--------|-------|------------|-------------|---------------------------|
| SURF   | 8.625 | 1721       |             | WITH 675 SX CMT           |
| COND   | 20    | 45         |             | 4 YDS-GROUT <b>195.03</b> |
| DVT    |       | 3100       |             | WITH 600 SX CMT           |
| PROD   | 5.5   | 6000       | 0           | WITH 1250 SX CMT          |

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/04/2009 9:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 100# HULLS & 25 SX CMT. PLUG AT 1750' WITH 25 SX CMT. PLUG AT 600' WITH 70 SX CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/04/2009 1:00 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

PUMP 200# HULLS & 25 SX CMT. 1ST PLUG AT 1750' WITH 25 SX CMT. 2ND PLUG AT 600' WITH 68 SX CMT. CMT TO SURFACE. PUMP 12 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS. PRESSURED TO 400 PSI.

Perfs:

| Top  | Bot  | Thru | Comments    |
|------|------|------|-------------|
| 4572 | 4576 |      | TPC @ 2720' |

RECEIVED  
NOV 10 2009  
KCC WICHITA

INVOICED  
DATE 12-28-09  
INV. NO. 2010060611

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

Signed

Jack MacClaskey  
(TECHNICIAN)

RECEIVED

NOV - 5 2009

KCC DODGE CITY