

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20733-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 35-19S-31W  
1650 feet from N Section Line, 990 feet from E Section Line  
Lease Name: ELINOR Well #: 1  
County: SCOTT Total Vertical Depth: 4725 feet

Operator License No.: 6569  
Op Name: SCHMITT, CARMEN, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		WITH 170 SX CMT

153.56

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/29/2009 5:00 PM  
Plug Co. License No.: 33935 Plug Co. Name: H. D. DRILLING, LLC  
Proposal Rcvd. from: DOUG ROBERTS Company: H. D. DRILLING, LLC Phone: (785) 372-5419

Proposed Plugging Method: 1ST PLUG AT 2280' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 100 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE  
Date/Time Plugging Completed: 10/29/2009 8:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG AT 2280' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 100 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

INVOICED  
DATE 10-28-09  
INV. NO. 2010060597

RECEIVED  
NOV 06 2009  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY OILWELL CEMENTING.

Plugged through: DP

District: 01

Signed

Steve Durrant  
(TECHNICIAN)

RECEIVED

NOV - 2 2009

KCC DODGE CITY