

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-01687-00-00  
Spot: SESESW Sec/Twnshp/Rge: 6-21S-13W  
312 feet from S Section Line, 2945 feet from E Section Line  
Lease Name: PARRISH Well #: 1  
County: STAFFORD Total Vertical Depth: 3670 feet

Operator License No.: 7054  
Op Name: DOONAN AND SONS, INC.  
Address: PO BOX 1466  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	246		WITH 125 SX CMT
PLG		3500		
PROD	4.5	3669	532	WITH 100 SX CMT

119.28

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/02/2009 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3400' & 4 SX CMT. PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/02/2009 9:35 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3400' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 800' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 270' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3634	3637		
3626	3631		
3456	3463		

INVOICED  
DATE 12-28-09  
INV. NO. 2010060599

RECEIVED  
NOV 06 2009

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

KCC WICHITA

Plugged through: TBG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
NOV - 3 2009  
KCC DODGE CITY

Form CD 73  
*[Signature]*