

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21459-00-00
Spot: W2NESE Sec/Twnshp/Rge: 13-22S-12W
1980 feet from S Section Line, 990 feet from E Section Line
Lease Name: WILLINGER Well #: 1
County: STAFFORD Total Vertical Depth: 3647 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3573		
SURF	8.625	316		WITH 275 SX CMT
PROD	5.5	3644	2427	N/A

118.53

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2009 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3490' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 350' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2009 9:34 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3460' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 620' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 373' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3612	3618		SIMPSON
3544	3550		KANSAS CITY

INVOICED
DATE 12-28-09
INV. NO. 2010060604

RECEIVED
NOV 06 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

RECEIVED
NOV - 2 2009
KCC DODGE CITY

Signed Richard W. Lacey
(TECHNICIAN)