

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22193-00-00
Spot: N2NWSWSW Sec/Twnshp/Rge: 18-22S-11W
1090 feet from S Section Line, 4950 feet from E Section Line
Lease Name: ROSS Well #: 2
County: STAFFORD Total Vertical Depth: 3652 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	344		WITH 250 SX CMT
PROD	5.5	3649	2370	WITH 150 SX CMT

118.69

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/26/2009 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND BOTTOM WITH 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 370' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/26/2009 1:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3500' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 605' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 373' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3649	3652	OH	

INVOICED
DATE 12-28-09
INV. NO. 2010060606

RECEIVED
NOV 06 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

RECEIVED
OCT 30 2009
KCC DODGE CITY

Signed Richard W. Lacey
(TECHNICIAN)

Form CP-2/3