

4-032042

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 1950

SE NW SW /4 SEC. 12 , 10 S, 21 W  
1650 feet from S section line  
4290 feet from E section line

Operator license# 5783

Lease Bass well # 2

Operator: Galloway Drilling Co., Inc.

County Graham

124.22

Address: 105 S. Broadway  
Suite #340  
Wichita, Kansas 67202

Well total depth 3822 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 255 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License#           

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 16 Month: January Year: 95

Plugging proposal received from: Dale

Company: Galloway Drilling Co., Inc. Phone:           

Were: Order 250 sxs. 60/40 pozmix - 10% gel - 500# hulls.  
Work string.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 1:00P.M., Day: 16, Month: January, Year: 95

Actual plugging report: 8 5/8" set at 255' w/150 sxs. cwc. 5 1/2" set  
at 3815' w/150 sxs. Squeezed at 1460' w/300 sxs. 5 1/2" has holes above  
and below squeeze. Critical area control shot at 1030'. Ran tubing to  
2240' - staged cement to surface - tied onto 5 1/2" squeezed with total  
of 200 sxs. cement blend with 400# hulls mixed into pos. P.S.I. 100#.  
Squeezed 8 5/8" with 50 sxs. cement blend with 100# hulls mixed into  
pos. P.S.I. 100#. Plug complete.

Remarks:           

Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO

Bottom plug(in place): YES , CALC , NO  Dakota plug: YES  NO

Plugged through TUBING , CASING . Elevation:            GL           

I did  did not  observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

INVOICED

DATE 2-1-95

INV. NO. 42123

1-16

MAR 16 1995

APR 26 1995

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 30 1995  
CONSERVATION DIVISION  
WICHITA, KANSAS