

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5783

Operator: GALLOWAY DRUG CO INC  
Name & 340 BROADWAY PLAZA BLDG.  
Address 105 S. BROADWAY  
WICHITA, KANSAS

15-065-01739-0000

API NUMBER 15-

SENESS, Sec. 12, T 10 S, R 21 W/E

feet from N/S section line

feet from W/E section line

Lease Name BASS Well # 5

County GRAHAM

Well Total Depth 3828 feet \$124.41

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor ALLIED CEM. License Number

Address PLAINVILLE, KS.

Company to plug at: Hour: PM Day: 26 Month: 4 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO DALE LOOMIS

(company name) GALLOWAY DRUG. (phone)

were: SQUEEZE DOWN 5 1/2" CASING WITH 50 SX. CEM - 28 SX GEL  
MIXED WITH 2 SX HULLS - 40 SX CEM. - 3 SX GEL - 5 1/2" WIDER PLUG - 25 SX CEM.  
800# MAX. 300# SHUT IN PSI

PUMPED 45 SX. CEM. DOWN ANNULUS OF 8 5/8" AND 5 1/2" 300# MAX PSI

CEM) 50/50 P02. 62 GEL 32 CC

Signed Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5:15 PM Day: 26 Month: 4 Year: 19 83

ACTUAL PLUGGING REPORT

AS ABOVE

Remarks: PERFORATED ANHYDRITE 4 SHOTS. HAD HOLES IN DAKOTA.

ELEV 2272

ANHY 1730

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

INVOICED

RECEIVED

DATE 5-9-83 STATE CORPORATION COMMISSION

INV. NO. 4224-W MAY 03 1983

Signed Carl Goodrow  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

CONSERVATION DIVISION  
Wichita, Kansas