

15-065-00312-0000 ✓ R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- _____

NWNWSW, Sec. 12, T 10 S, R 21 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5783

Lease Name BASS Well # 1

Operator: GALLOWAY DRLG. CO. INC.
Name & Address: 340 BROADWAY PLAZA BLDG.
105 S. BROADWAY
WICHITA, KANSAS

County GRAHAM

Well Total Depth 3831 feet \$124.51

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 228

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor ALLIED CEM. License Number _____

Address PLAINVILLE, KS.

Company to plug at: Hour: PM Day: 26 Month: 4 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO DALE LOOMIS

(company name) GALLOWAY DRLG. (phone) _____

were: SQUEEZE DOWN 5 1/2" CASING WITH (25X HULLS)-50 SX CEM
28 SX GEL. (MIXED WITH HULLS) 40 SX. CEM-3 SX GEL. 25 SX CEM. 5 1/2" PLUG
RELEASED AHEAD OF LAST BATCH OF CEMENT. 800# MAX. 300# SHUT IN PSI
PUMP 45 SX CEM. DOWN BACK SIDE (ANNULUS - 8 5/8 & 5 1/2) 300# MAX PSI

CEM > 50/50 po2 6% GEL 32 CC

Signed Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 PM Day: 26 Month: 4 Year: 1983

ACTUAL PLUGGING REPORT _____

AS ABOVE

Remarks: CASING HAD HOLES IN DAKOTA TO ANHYDRITE

ELEV. 2272

ANHY 1730

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED
DATE 5-9-83
INV. NO. 4225-W

RECEIVED
STATE CORPORATION COMMISSION
MAY 03 1983
CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82