

6-27 15-065-19154-00-01

6 031123

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1950  
SW SE SW, SEC. 2, T 10 S, R 21 W/8  
330 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
5153  
Operator License #

Operator: Texaco Inc.  
Name & Address: Star Route Box  
Russell, Ks. 67665

Lease Name V. V. White Well # 5  
County Graham 123.47  
Well Total Depth 3799 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well  Gas Well  Input Well  SWD Well  U&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Hays, Ks.

Company to plug at: Hour: PM Day: 27 Month: June Year: 19 88

Plugging proposal received from Earl

(company name) Texaco (phone)

were: 8 5/8" set at 285' w/150 sks cwc. 5 1/2" set at 3792' w/200 sks.

PBTD 3783'. Perfs 3560' - 3781'. Squeezed at 1300' w/150 sks. Shot at 1705' - 06' Anhy Block squeeze. Order 300 sks Cement Blend w/500# Hulls. Halliburton Cement Co.

OWS Water Trucks..

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:10PM Day: 27 Month: June Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" w/250 sks Cement. To max Psi 600#. Close in Psi 600#. Squeezed 8 5/8" w/50 sks cement to max Psi 600#. Close in 600#. Plug complete.

RECEIVED CORPORATION COMMISSION

6 1988

16-1988

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

Signed Carl Goodrow (TECHNICIAN)

D

Carl Goodrow

DATE 9-21-88

INV. NO. 22341 NOV 15 1988

FORM CP-2/3 Rev. 01-84