

7-23 15-065-01662-00-00 210P

To: 6 031569  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1951  
SE <sup>NW</sup> ~~NW~~ <sup>NE</sup>, SEC. 2, T 10 S, R 21 <sup>W/E</sup>  
~~4290~~ 4290 feet from S section line  
~~1650~~ 4290 feet from E section line

AJB  
KCC

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5229  
Operator: Phillips Pet. Company  
Name & Address: Rt. 3 Box 20-A  
Great Bend, Kansas 67530

Lease Name Noah Well # 3  
County Graham 124.93  
Well Total Depth 3838' feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size \_\_\_\_\_ feet

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Chase, Kansas

Company to plug at: Hour: P.M. Day: 23 Month: 7 Year: 19 91

Plugging proposal received from Bill  
(company name) Kelso (phone) \_\_\_\_\_

were: 8 5/8 set @ 1771' w/975 sx. cwc. 5 1/2 set @ 3807' w/200 sx. O.H. 3807' - 38'.  
Order sand and common cement. Pull pipe. Order 225 sx. 65/35 poz. 10% gel.  
500 hulls. Allied Cement Company. Bennie Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:45 P.M. Day: 23 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT Sand back to 3750' w/5 sks. common cement on sand w/bailer.

Recovered 2018' of 5 1/2 casing. Squeezed 8 5/8 w/225 sx. cement blend w/500# hulls mixed in to max P.S.I. 500#. Close in P.S.I. 200 #. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 21 1991  
8-21-1991

Remarks: (If additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED observe this plugging.

DATE 9-5-91  
INV. NO. 32951

J.H.S.

Signed Carl Goodrow (TECHNICIAN)