

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 2-10-55

6 040947

15-065-03026-00-01 40 & R
9-22

SE SE NE, SEC. 5 1/4, T 10 S, R 21 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 8677

Operator: Kanco Inc. of Kansas Lease Name Rudman Well # 1
Name & Address Box 177 County Graham 127.99
Russell, Ks. 67665

RECEIVED
STATE CORPORATION COMMISSION
11-8-1988
NOV 8 1988
CONSERVATION DIVISION
Wichita, Kansas

Well Total Depth 3938 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 185' w/175 sk

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address Russell, Ks.

Company to plug at: Hour: 2:00PM Day: 22 Month: Sept Year: 19 88

Plugging proposal received from Elmer Froelich

(company name) Kanco (phone) _____

were: 5 1/2" casing set at 3938'. Top perf at 3552'. Perf anhy at

1610' and base Dakota at 1000'. Ordered 275 sks 60/40 Poz 8% Gel plus 12 sks gel w/1/4# F.C. plus 6 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30PM Day: 22 Month: Sept Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 225 sks cement w/1/4# F.C. plus

4 sks Hulls mixed in cement. Max 500#. S.I. 200# Psi. Pumped in 8 5/8" casing 50 sks

cement w/1/4# F.C. plus 2 sks Hulls mixed in cement. Max 400# S.I. 200# psi.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel

DATE 11-9-88
INV. NO. 22958